

Item	Description	Quantity	Unit	Rate	Amount
	<u>Godre'r Graig Primary School Road Widening</u>				
1	Prelims including road sweeping and security	1	sum	24,009.66	24,009.66
2	Traffic management	1	sum	1,128.40	1,128.40
3	Excavate to formation 450mm thick and disposal	245	m2	50.69	12,419.05
4	PCC gully + 150mm 6m long connection to existing MH in access road	2	no	1,199.14	2,398.28
5	HB2 kerbs	70	m	40.36	2,825.20
6	Type 1 sub-base 250mm thick	245	m2	33.56	8,222.20
7	Base course 100mm thick	245	m2	22.57	5,529.65
8	Binder course 60mm thick	245	m2	16.93	4,147.85
9	Surface course 40mm thick	245	m2	14.11	3,456.95
10	Road Markings	1	item	902.72	902.72
	Pricing Notes Service diversions by other (telegraph pole adjacent to school car park gates) Inert waste				
Page 1		Total to Series Summary			65,039.96

Item	Description	Quantity	Unit	Rate	Amount
	<p><u>Godre'r Graig Primary School Road Widening (Cont'd)</u></p> <p>Series Summary</p> <p>Page 1</p>				65,039.96
<p>Page 3</p> <p>Total to Grand Summary</p>					65,039.96

Item	Description	Quantity	Unit	Rate	Amount
	<u>GRAND SUMMARY</u>				
	Godre'r Graig Primary School Road Widening				65,039.96
GS	Page 1	GRAND TOTAL			65,039.96